



REQUEST FOR PROPOSALS

Central Oregon Community College

Solar Carport Project

RFP DATE: January 29, 2025

SITE VISIT (Optional): February 14, 2025, 1:00 pm

DUE DATE: March 3, 2024 at 5:00 PM (PST)

NOTICE OF AWARD: March 31, 2025 (expected)

Contact:

Dan Orzech

Oregon Clean Power Cooperative

dan@oregoncleanpower.coop

(610) 650-7755

Introduction

Central Oregon Community College (COCC) in partnership with the Oregon Clean Power Cooperative (Oregon Clean Power), received a 2023 ODOE CREP Grant for a 51 kW net metered solar project at COCC's Madras campus. A ground mount location was deemed not viable due to the rocky soil conditions, and the roof was determined to be not suitable. This RFP is for construction of a solar carport. No battery storage is planned for the project.

This Request for Proposals (RFP) seeks to identify a contractor able to provide the most timely and cost-effective solar installation for the project. The contractor selected will execute a construction contract with the Oregon Clean Power Co-op, which will own the project, and sell the power generated to COCC under an executed Power Purchase Agreement. The Oregon Solar Installation Specialty Code in addition to state and local codes will apply, and the project must meet COCC construction standards.

Location

The project is located at:
1170 E. Ashwood Rd.
Madras, OR 97741

Central Oregon Community College was founded in 1949, and is the longest standing community college in Oregon. The Madras campus was opened in 2011. An additional building, located to the west of the current building, is currently under construction, but is not expected to conflict with the solar carport project.

The proposed solar carport PV array will be installed in the SE Parking Lot on the East side of the COCC Madras campus (see Figure 1).




Figure 1: Solar carport location.

Scope of Work

The contractor selected will provide a turnkey, installed and operational solar PV carport system which provides the maximum reasonable amount of energy generated, at the lowest possible cost.

We seek the earliest possible date of installation of the system, understanding that delays cannot always be anticipated.

A feasibility study, attached as Attachment A, generated a preliminary design with a 52 kW solar carport at a 244-degree azimuth. Inverters fed into an outdoor combiner panel, and connecting to the existing building with a 200A supply-side disconnect. Conduit(s) from the carport array to the Madras building

CT cabinet will require excavation from the array site through a finished parking lot, concrete sidewalk, planter, etc. Full restoral of these areas is required under this project scope with equal or better materials. See site plans, attached aa Attachment B. Plans are for informational purposes only.

Contractor will be required to provide engineered drawings suitable for Jefferson County, Oregon, plan review, provide locates, purchase all necessary permits and finalized inspections with all AHJ's; provide all materials, provide all labor, provide all necessary sub-contractors, all project management, and licensing for a true turn-key installation.

Systems shall include monitoring and commissioning, and contractor shall be responsible for ensuring that the system passes all required inspections and meets all COCC and other applicable requirements. Contractor shall also be responsible for ensuring that applications have been properly submitted for Energy Trust of Oregon incentives and Pacific Power net metering. Monitoring must be fully functional before final payment to Contractor will be make.

Size

Minor variations in size are allowed, but array designs smaller than 51 kW may result in the amount of the ODOE CREP being reduced and are discouraged.

Equipment Selection

Contractor will be responsible for evaluating and selecting all equipment provided. No additional points will be awarded for domestically-manufactured equipment. Any established solar carport brand is acceptable, including but not limited to Terrasmart, Polar Racking or Baja.

Contractor shall ensure that inverter(s) selected provide a public or "kiosk" monitoring view, with a link posted on the websites of COCC and Oregon Clean Power.

Proposals must include Contractor's Installation Warranty period, Product Warranties, and Performance Warranty.

Construction Requirements

Contractors will be required to meet all applicable code requirements. All costs associated with the construction of the solar electric system, including insurance coverage, will be the responsibility of the contractor. The contractor shall furnish all labor, materials, permits, transportation, storage, and equipment rental costs to construct the entirety of the solar electric system in accordance with the final approved plans and specifications for the project site.

In the installation of the solar electric system, the contractor and its subcontractors must comply with ORS 279C.800 through 279C.870 which will require the payment of BOLI prevailing wage rates to workers on the installation project.

Construction shall include the cost of power system components and installation of the solar power system (including tie-ins to the existing utility electric service in accordance with the net metering and interconnection agreements with Pacific Power). Any and all wall penetrations must be done by a licensed contractor and must be repaired to the satisfaction of COCC.

Proposal Submittal and Contents

Proposals shall be emailed in PDF format to info@oregoncleanpower.coop. If there are issues with emailing, files may instead be uploaded upon request to a Google Drive or Box.com folder. Proposals submitted on paper will not be accepted.

Please limit proposals to a total of 12 pages, not including manufacturers equipment specification sheets. Brevity and clarity in the proposals are appreciated.

Proposals shall include:

- 1) A brief list of related project experience, including location, customer and project size, and any other relevant details.
- 2) Resumes or statement of qualifications of key personnel, no longer than one page each.
- 3) Proposed solar carport design.
- 4) Production estimates.
- 5) Proposed equipment, including spec sheets.
- 6) Estimated date of project start and completion.
- 7) Pricing for a turnkey, installed system in both \$/W and dollars.
- 8) Warranty information for equipment and workmanship.
- 9) Any other relevant information.

Oregon Clean Power reserves the right to obtain clarification of any point in a proposal or to obtain additional information necessary to evaluate a particular proposal.

Evaluation Criteria

Proposals shall be evaluated based on the following criteria:

Price: 50%

Equipment proposed: 30%

Similar project experience & Project team: 20%

Oregon Clean Power intends to select a proposal which serves the best interests of the itself and COCC and reserves the right to reject any or all proposals, and waive any informalities or irregularities.

Site Visit

An option site visit is scheduled for Friday, February 14, 2025, at 1:00 pm. It is suggested that interested bidders confirm before arrival.

Questions

Send to info@oregoncleanpower.coop with the project name in the Subject line.

Updates

Updates, if any, will be posted to www.oregoncleanpower.coop.

ARRAY SPECIFICATIONS
 (104) SILFAB SIL-500HM 500W PV MODULES
 (2) SOLECTRIA PVI-25TL-208 INVERTERS

ARRAY
 5° TILT
 244° AZIMUTH
 4X26 MODULES

CARPORTS SPECIFICATIONS
 METAL PURLINS
 PITCH: 5°
 AZIMUTH: 244°



SUNBREAK ENERGY ADVISORS
 3504 SW JERALD CT.
 PORTLAND, OR 97221
 P: 503-803-5537
 SUNBREAKENERGY.COM
 CCB #240886

COCC MADRAS
 CENTRAL OREGON COMMUNITY COLLEGE

COCC MADRAS

PROJECT DESCRIPTION
 52.0kW SOLAR PV PROJECT
 PROJECT ADDRESS
 1170 ASHWOOD RD, BLDG 1
 MADRAS, OR 97741

CONTACT INFORMATION
 RANDY FELDHAUS
 503-803-5537
 randy@sunbreakenergy.com

SITE PLAN

REVISION	DATE	REASON


DESIGNED BY
RANDY FELDHAUS

DRAWN BY
SEPHORA MORALES

DRAWN ON
7/5/24

SCALE
1" = 50'

SHEET NUMBER
A1.0





SUNBREAK ENERGY ADVISORS
 3504 SW JERALD CT.
 PORTLAND, OR 97221
 P: 503-803-5537
 SUNBREAKENERGY.COM
 CCB #240886

COCC MADRAS
 CENTRAL OREGON COMMUNITY COLLEGE

COCC MADRAS

PROJECT DESCRIPTION
 52.0kW SOLAR PV PROJECT
 PROJECT ADDRESS
 1170 ASHWOOD RD, BLDG 1
 MADRAS, OR 97741

CONTACT INFORMATION
 RANDY FELDHAUS
 503-803-5537
 randy@sunbreakenergy.com

WIRING DIAGRAM

REVISION	DATE	REASON


DESIGNED BY
RANDY FELDHAUS

DRAWN BY
SEPHORA MORALES

DRAWN ON
 7/5/24

SCALE
 NTS

SHEET NUMBER
E1.0



SUPPLY-SIDE CONNECTION TO BE IN PACIFIC POWER CT CABINET.
 PERMISSION MUST BE GRANTED BY PACIFIC POWER TO CONNECT
 WITH CT CABINET.

SYSTEM INFORMATION

MODULE SPECIFICATION	
MODEL	SILFAB SIL-500 HM
MODULE POWER @ STC	500W
OPEN CIRCUIT VOLTAGE:Voc	45.78V
MAX POWER VOLTAGE:Vmp	38.80V
SHORT CIRCUIT VOLTAGE:Isc	13.48A
MAX POWER CURRENT:Imp	12.89A

INVERTER SPECIFICATION	
MODEL	SOLECTRIA PVI-25TL-208
POWER RATING	25.0kW
MAX CONTINUOUS OUTPUT CURRENT	69.5A
CEC WEIGHTED EFFICIENCY	96.5%
MAX DC POWER	45.0kW
MAX DC VOLTAGE	1000V



SUNBREAK ENERGY ADVISORS
3504 SW JERALD CT.
PORTLAND, OR 97221
P: 503-803-5537
SUNBREAKENERGY.COM
CCB #240886

COCC MADRAS
CENTRAL OREGON COMMUNITY
COLLEGE

WIRE CALCULATIONS

AC WIRE CALCULATIONS: -MATERIAL:COPPER & TEMPERATURE RATING:90°C

CONDUIT SCHEDULE

TAG ID	REQUIRED CONDUCTOR AMPACITY									CORRECTED AMPACITY CALCULATION						TERMINAL RATING CHECK			DERATED CONDUCTOR AMPACITY CHECK			75C AMPACITY	LENGTH	VDROP	
1	12.89	X	1	=	12.89	X	1.25	=	16.11A	40	X	0.96	X	0.5	=	19.20A	16.11A	<	35A	16.11A	<	19.20A	35A	90	1.33%
2	69.50	X	1	=	69.50	X	1.25	=	86.88A	115	X	0.96	X	1.0	=	110.40A	86.88A	<	100A	86.88A	<	110.40A	100A	5	0.07%
3	139.00	X	1	=	139.00	X	1.25	=	173.75A	225	X	1.00	X	1.0	=	225.00A	173.75A	<	200A	173.75A	<	225.00A	200A	150	1.52%
4	139.00	X	1	=	139.00	X	1.25	=	173.75A	195	X	0.96	X	1.0	=	187.20A	173.75A	<	175A	173.75A	<	187.20A	175A	5	0.07%

VOLTAGE DROP SUMMARY
TOTAL DC VOLTAGE DROP: 1.33%
TOTAL AC VOLTAGE DROP: 1.66%

CONDUIT SCHEDULE

TAG ID	CONDUIT SIZE	CONDUCTOR	NEUTRAL	GROUND
1	NONE	(12) 10 PV WIRE CU	NONE	(1) 6AWG BARE COPPER
2	1.25" EMT OR EQUIV	(3) 3AWG THHN/THWN-2	(1) 8AWG THHN/THWN-2	(1) 8AWG THHN/THWN-2
3	2" PVC-40 OR EQUIV	(3) 3/0AWG THHN/THWN-2	(1) 4AWG THHN/THWN-2	(1) 4AWG THHN/THWN-2
4	1.5" EMT OR EQUIV	(3) 2/0AWG THHN/THWN-2	(1) 6AWG THHN/THWN-2	(1) 6AWG THHN/THWN-2

705.11(A) Service Connections.
An electric power production source shall be permitted to be connected to a service by one of the following methods:
(1) To a new service in accordance with 230.2(A)
(2) To the supply side of the service disconnecting means in accordance with 230.82(6)
(3) To an additional set of service entrance conductors in accordance with 230.40, Exception No.5
These connections shall comply with 705.11(B) through (F).

COCC MADRAS

PROJECT DESCRIPTION
52.0kW SOLAR PV PROJECT
PROJECT ADDRESS
1170 ASHWOOD RD, BLDG 1
MADRAS, OR 97741

CONTACT INFORMATION
RANDY FELDHAUS
503-803-5537
randy@sunbreakenergy.com


WIRE CALCS

REVISION	DATE	REASON

DESIGNED BY
RANDY FELDHAUS
DRAWN BY
SEPHORA MORALES
DRAWN ON
7/5/24
SCALE
NTS
SHEET NUMBER
E2.0

COCC Madras 1 Carport 1170 E Ashwood Rd, Bldg 1, Madras OR 97741

Shading Heatmap



Shading by Field Segment


Description	Tilt	Azimuth	Modules	Nameplate	Shaded Irradiance	AC Energy	TOF ²	Solar Access	Avg TSRF ²
Field Segment 1	5.0°	244.0°	104	52.0 kWp	1,648.4kWh/m ²	68.1 MWh ¹	85.1%	99.6%	84.7%
Totals, weighted by kWp			104	52.0 kWp	1,648.4kWh/m²	68.1 MWh	85.1%	99.6%	84.7%

¹ approximate, varies based on inverter performance
² based on location Optimal POA Irradiance of 1,945.8kWh/m² at 39.6° tilt and 182.5° azimuth


Solar Access by Month

Description	jan	feb	mar	apr	may	jun	jul	aug	sep	oct	nov	dec
Field Segment 1	99%	99%	99%	100%	100%	100%	100%	100%	100%	99%	99%	98%
AC Power (kWh)	2,020.5	3,350.1	5,424.5	6,912.7	8,631.1	9,045.5	9,651.9	8,127.7	6,513.4	4,336.2	2,332.2	1,749.7


Monthly Production




Sources of System Loss



Southwestern Angle






Southeastern Angle



COCC Madras 1 Carport COCC Madras 1, 1170 E Ashwood Rd, Bldg 1, Madras OR 97741

Report	
Project Name	COCC Madras 1
Project Address	1170 E Ashwood Rd, Bldg 1, Madras OR 97741
Prepared By	Randall Feldhaus randy@sunbreakenergy.com

System Metrics	
Design	COCC Madras 1 Carport
Module DC Nameplate	52.0 kW
Inverter AC Nameplate	50.0 kW Load Ratio: 1.04
Annual Production	68.10 MWh
Performance Ratio	79.1%
kWh/kWp	1,309.5
Weather Dataset	TMY, 10km Grid (44.65,-121.15), NREL (prospector)
Simulator Version	7330c4b3fe-6fd40504ac-080d2e95e1-18f6275ff1



⚡ Annual Production			
	Description	Output	% Delta
Irradiance (kWh/m ²)	Annual Global Horizontal Irradiance	1,627.0	
	POA Irradiance	1,655.1	1.7%
	Shaded Irradiance	1,648.4	-0.4%
	Irradiance after Reflection	1,582.7	-4.0%
	Irradiance after Soiling	1,551.0	-2.0%
	Total Collector Irradiance	1,551.0	0.0%
Energy (kWh)	Nameplate	80,675.3	
	Output at Irradiance Levels	80,218.1	-0.6%
	Output at Cell Temperature Derate	74,238.6	-7.5%
	Output After Mismatch	71,336.2	-3.9%
	Optimal DC Output	71,150.8	-0.3%
	Constrained DC Output	71,148.7	0.0%
	Inverter Output	68,658.5	-3.5%
	Energy to Grid	68,095.4	-0.8%
Temperature Metrics			
	Avg. Operating Ambient Temp		11.4 °C
	Avg. Operating Cell Temp		28.4 °C
Simulation Metrics			
	Operating Hours		4708
	Solved Hours		4708


☁ Condition Set												
Description	Condition Set 1											
Weather Dataset	TMY, 10km Grid (44.65,-121.15), NREL (prospector)											
Solar Angle Location	Meteo Lat/Lng											
Transposition Model	Perez Model											
Temperature Model	Sandia Model											
Temperature Model Parameters	Rack Type	a	b	Temperature Delta								
	Fixed Tilt	-3.56	-0.075	3°C								
	Flush Mount	-2.81	-0.0455	0°C								
	East-West	-3.56	-0.075	3°C								
	Carport	-3.56	-0.075	3°C								
Soiling (%)	J	F	M	A	M	J	J	A	S	O	N	D
	2	2	2	2	2	2	2	2	2	2	2	2
Irradiation Variance	5%											
Cell Temperature Spread	4° C											
Module Binning Range	-2.5% to 2.5%											
AC System Derate	0.50%											
Module Characterizations	Module						Uploaded By		Characterization			
	SIL-500 HM (Silfab Solar Inc.)						HelioScope		Spec Sheet Characterization, PAN			
Component Characterizations	Device						Uploaded By		Characterization			
	PVI 25TL-208 (Solectria)						HelioScope		Spec Sheet			

📦 Components		
Component	Name	Count
Inverters	PVI 25TL-208 (Solectria)	2 (50.0 kW)
AC Home Runs	2 AWG (Copper)	2 (1,474.5 ft)
Strings	10 AWG (Copper)	6 (639.5 ft)
Module	Silfab Solar Inc., SIL-500 HM (500W)	104 (52.0 kW)

🔌 Wiring Zones			
Description	Combiner Poles	String Size	Stringing Strategy
Wiring Zone	-	13-19	Along Racking

🏠 Field Segments									
Description	Racking	Orientation	Tilt	Azimuth	Intrarow Spacing	Frame Size	Frames	Modules	Power
Field Segment 1	Flush Mount	Portrait (Vertical)	5°	244°	0.0 ft	1x1	104	104	52.0 kW

Detailed Layout





- ### KEY NOTES
- EXISTING FENCE TO BE REMOVED
 - TRANSFORMER, MAINTAIN 3'-0" CLR. - SEE CIVIL FOR RETAINING WALL REQUIREMENTS - SEE ELECTRICAL DRAWINGS
 - SITE LIGHTING - SEE ELECTRICAL DRAWINGS
 - RIP RAP DAYLIGHT OUTFALL AT RETENTION SWALE, SEE CIVIL FOR CONTINUATION AND 4' FLUMBING
 - CLEAR VISION AREA
 - BIKE PARKING, (4) 2 STALL RACKS, OF/C.I. SEE DETAIL 6/A103
 - NEW 5'-0" WIDE SIDEWALK, EXTEND TO STREET
 - 5' WIDE PEDESTRIAN CROSSING STRIPING - SEE CIVIL DRAWINGS
 - PROJECT CONSTRUCTION SIGN - SEE DETAIL 23/A103
 - EXISTING TREES TO REMAIN, PROVIDE PROTECTION TO TREES SCHEDULED TO REMAIN WITHIN THE LIMITS OF WORK. USE BEST PRACTICES TO MAINTAIN TREES IN A HEALTHY CONDITION
 - EXISTING TREES TO BE REMOVED
 - LIMITS OF WORK
 - RELOCATED WATER METER
 - FIRE HYDRANT - SEE CIVIL DRAWINGS
 - ADA PARKING SIGN - SEE DETAIL 11/A103
 - TRASH/RECYCLING ENCLOSURE - SEE DETAIL 1/A103
 - 4' WHITE PARKING STALL STRIPING, PER CITY STANDARDS
 - CONCRETE CONTROL JOINTS, SEE DETAIL 19/A103
 - ASPHALT PAVING - SEE CIVIL DRAWINGS
 - CONCRETE CURB, SEE CIVIL DRAWINGS
 - FUTURE PATH BY CITY
 - ACCESSIBLE ROUTE TO PUBLIC WAY
 - CONSTRUCTION STAGING AREA
 - KNOX BOX, SEE DETAIL 22/A103
 - ASSUMED PROPERTY LINE
 - NEW 5'-0" WIDE ASPHALT PATH - BY OTHERS
 - TRASH & ASH RECEPTACLE
 - WHEEL STOPS - SEE CIVIL DRAWINGS
 - DEDUCTIVE ALTERNATE BUILDING OUTLINE, SEE A201a, A202a, A401
 - FIRE RISER ROOM (BASE BID)
 - NEW COMPACTED GRAVEL SURFACE
 - DRAINAGE RETENTION SWALE - SEE CIVIL DRAWINGS
 - FLAG POLE WITH CONC. BASE - PROVIDE POWER FOR LIGHTING
 - CURB BREAK AND CONCRETE AREA W/ RIP RAP - SEE CIVIL DRAWINGS
 - DETECTABLE WARNING STRIP
 - 15 MIN PARKING SIGN - SEE DETAIL 13/A103
 - PEDESTRIAN CROSSING NON-ADA
 - AREA OF SNOW MELT SYSTEM - SEE ELECTRICAL SITE PLAN
 - ROUTE FOOTING DRAINS TO DAYLIGHT ABOVE OVERFLOW LINE OF STORM WATER RETENTION POND.
 - ACCESS CONTROL SIGN - SEE DETAIL 12/A103

- ### GENERAL NOTES
- REFER TO CIVIL DRAWINGS FOR HORIZONTAL CONTROL INFORMATION, DRAINAGE, FLOOR AND PAVING ELEVATIONS, AND SITE UTILITIES. REFER TO STRUCTURAL DRAWINGS FOR FOUNDATION AND SLAB DESIGN. REFER TO MECHANICAL, PLUMBING, LANDSCAPE AND ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.
 - FOLLOW ALL RECOMMENDATIONS AND REQUIREMENTS OF THE GEOTECHNICAL INVESTIGATION UNLESS MORE STRINGENT REQUIREMENTS APPEAR IN THESE CONTRACT DOCUMENTS AND SPECIFICATIONS.
 - LIMITS OF WORK: THE CONTRACTOR SHALL CONFINE OPERATIONS AT THE SITE TO AREAS PERMITTED BY LAW, ORDINANCES, PERMITS AND THE CONTRACT DOCUMENTS. HE SHALL NOT UNREASONABLY ENCLUMBER THE SITE WITH MATERIALS AND/OR EQUIPMENT.
 - STAGING AREA: THE CONTRACTOR AND SUBCONTRACTORS SHALL LIMIT STORAGE OF MATERIALS AND PORTABLE FIELD OFFICES WITHIN THE AREAS APPROVED BY THE CITY OF MADRAS AND THE OWNER. CONTRACTOR TO MAINTAIN ACCESS TO, FROM AND THROUGH PUBLIC WAYS.
 - GENERAL CONTRACTOR SHALL TAKE CARE NOT TO DAMAGE OR DISRUPT EXISTING UTILITIES, INCLUDING DRAINS WHILE EXCAVATING OR GRADING DURING CONSTRUCTION. CONFIRM LOCATION OF EXISTING UTILITIES OF ADJACENT PROPERTIES. CALL BEFORE YOU DIG.
 - THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING THE ACCUMULATION OF WATER OR DAMAGE TO ANY FOUNDATIONS ON THE PREMISES OR THE ADJACENT PROPERTIES SURROUNDING THE PROJECT SITE. (OSBC 2004, SECTION 33012)
 - PRIOR TO START OF WORK THE CONTRACTOR SHALL COORDINATE WITH EACH RESPECTIVE GOVERNING AUTHORITY IN VERIFYING THE LOCATION (VERT. ELEVATIONS, HORIZONTAL CONTROLS, EASEMENTS) OF EXISTING SANITARY AND STORM SEWER, WATER, NATURAL GAS, ELECTRICAL, FIBER OPTIC, TELEPHONE, OVERHEAD POWER LINES AND OTHER UTILITY SYSTEMS, BOTH ON-SITE AND OFF-SITE. THE CONTRACTOR SHALL CAREFULLY COMPARE THE UTILITY INFORMATION WITH THE CONTRACT DOCUMENTS. IF A CONSTRUCTION CONFLICT IS DISCOVERED BETWEEN THE UTILITY INFORMATION OBTAINED AND THE CONTRACT DOCUMENTS NOTIFY THE ARCHITECT IMMEDIATELY.
 - UNLESS NOTED OTHERWISE SIDEWALKS AND RAMPS SHALL BE CONSTRUCTED TO THE FOLLOWING REQUIREMENTS:
 - MAX. CROSS SLOPE OF SIDEWALKS & LANDINGS: 1:50
 - MAXIMUM SLOPE OF SIDEWALKS: 1:20
 - MAXIMUM SLOPE OF RAMPS: 1:12
 - MAXIMUM SLOPE OF DISABLED PARKING STALLS: 2% IN ANY DIRECTION
 - 2% MAXIMUM SLOPE FOR 5'-0" IN DIRECTION OF TRAVEL AT ALL BUILDING ENTRANCES
 - EMERGENCY VEHICLE ACCESS: THE CONTRACTOR SHALL MAINTAIN FIRE TRUCK ACCESS TO THE SITE THROUGHOUT THE CONSTRUCTION PROCESS UNLESS AN ALTERNATE PLAN IS APPROVED IN WRITING BY THE FIRE DEPARTMENT.
 - SEE PLANS AND ELEVATIONS FOR DETAILED LOCATION AND SIZE OF GLAZING AND BUILDING ENTRANCES
 - REFER TO CIVIL DRAWINGS FOR HORIZONTAL CONTROL INFORMATION
 - REFER TO CIVIL DRAWINGS FOR PAVEMENT SECTION DESIGN
 - ALL CURB RADII SHOWN ON PLAN TO BE 30" TO OUTSIDE FACE OF CURB UNLESS OTHERWISE INDICATED.

1 SITE PLAN
SCALE: 1" = 20' - 0"

BUILDING / SITE DATA

SITE DATA:		ACCESSIBLE SPACES	
SITE: (14.93 AC)	650,559 SF	REQUIRED (OSBC 1104.1)	
BUILDING:	9,165 SF	INCLUDING VAN ACCESSIBLE	4
ASPHALT PARKING LOT:	21,993 SF	PROVIDED	4
CONCRETE WALKS:	6,600 SF		
GRAVEL PARKING LOT:	12,944 SF		
LANDSCAPING:			
REQUIRED (15% MIN)	91,584 SF	BICYCLE PARKING (4.1, C)	1
PROVIDED (91.4%)	594,846 SF	REQUIRED	8
		PROVIDED	
BUILDING LOT COVERAGE:	14%	LOADING SPACES	
IMPERVIOUS LOT COVERAGE:	6.7%	REQUIRED	0
(BLDG. + PAVING)	9,165 + 34,592 = 43,757 SF	PROVIDED	0
ZONE: OPEN SPACE/ PUBLIC FACILITIES (OS/FF)		SITE LIGHTING:	
BUILDING HEIGHT:		SITE LIGHTING SHALL PROVIDE 1 FOOT-CANDLE (MIN) AT ALL ACCESSIBLE AREAS AND EGRESS PATHS	
ALLOWABLE 35' (8-12.3.B, D)	35 FEET	SIGNAGE:	
DESIGN HEIGHT	18-26 FEET	SIGNAGE SHALL CONFORM TO CITY OF MADRAS STANDARDS. EXTERIOR SIGNAGE, OTHER THAN BUILDING SIGN, IS NOT IN CONTRACT.	
SETBACKS:		NONE	
OFF-STREET PARKING:		ALL REQUIRED PARKING IS PROVIDED ON-SITE.	
COMMERCIAL ADULT SCHOOL USE:			
SPACES REQUIRED (BASED ON CITY MEETING 10-07-10)			
TOTAL SPACES REQUIRED		65	
TOTAL SPACES PROVIDED		102	
		10 PAVED SPACES	
		30 GRAVELED SPACES	

SYMBOLS LEGEND

	LIMITS OF WORK		ACCESSIBLE ROUTE TO PUBLIC WAY
	ASSUMED PROPERTY LINE		FOUNDATION VENTILATION WELL
	NEW CONCRETE PATIO, INTEGRAL COLOR W/ LIGHT BASKET WEAVE BROOM FINISH PATTERN, ARROW INDICATES DIRECTION OF FINISH		NEW FIRE HYDRANT - SEE CIVIL DRAWINGS
	NEW CONCRETE SIDEWALK, LIGHT BROOM FINISH - CONTROL JOINTS @ 5'-0" O.C.		CURB BREAK WITH RIP RAP - SEE CIVIL
	NEW COMPACTED GRAVEL SURFACE - SEE CIVIL		RIP RAP DAYLIGHT OUTFALL - SEE CIVIL
	NEW ASPHALT PAVING, SEE CIVIL		SNOW MELT SYSTEM - SEE ELECTRICAL SITE PLAN
	NEW SITE LIGHTING, SEE ELECTRICAL DRAWINGS		FLAG POLE WITH CONCRETE BASE - PROVIDE POWER FOR LIGHTING
	EXTERIOR BUILDING LIGHTING, SEE ELECTRICAL DRAWINGS		
	NEW TRANSFORMER		
	BUILDING ACCESSIBLE ENTRY/EGRESS		
	WATER METER, SEE CIVIL		
	ELECTRICAL METER, SEE ELECTRICAL SITE PLAN		
	GAS METER, SEE PLUMBING		
	FIRE DEPARTMENT CONNECTION, SEE CIVIL DRAWINGS		
	POST INDICATOR VALVE, SEE CIVIL DRAWINGS		

changed Per PR#15
Posted on 12/20

COPYRIGHT 2010
STEELE ASSOCIATES ARCHITECTS LLC
All rights reserved. Reproduction or use in any form or by any means - graphic, electronic, mechanical, etc. - without written permission of STEELE ASSOCIATES ARCHITECTS LLC is unlawful and subject to criminal prosecution.

REGISTERED ARCHITECT
3315
SCOTT T. STEELE
info@steele-arch.com
BEND, OREGON

STEELE ASSOCIATES
ARCHITECTS LLC
760 NW YORK DRIVE, SUITE 200
BEND, OR 97701
541.382.9867 FAX 541.385.8816
info@steele-arch.com

COCC MADRAS CAMPUS
EDUCATION CENTER
MADRAS, OREGON

ASHWOOD ROAD
SITE PLAN

ISSUED	DATE
JOB NO. 12110201	
DATE 12/28/10	
DRAWN BY JT, DR, CS, ES	CHECKED BY JUL, STB
REVISIONS	DATE
1. CITY COMMENTS	02/11/11

SHEET NO. **A101** SHEETS

CONSTRUCTION SET - 02/11/11

KIRBY NAGELROTH CONSTRUCTION COMPANY
 3800 SW 10th Ave
 Bend, OR 97701
 Tel: (503) 325-8811
 Fax: (503) 325-8811

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

KIRBY NAGELROTH CONSTRUCTION COMPANY
 3800 SW 10th Ave
 Bend, OR 97701
 Tel: (503) 325-8811
 Fax: (503) 325-8811

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

Jeff Wellman
 Project Superintendent
 Kirby Nagelroth Construction Co.
 3800 SW 10th Ave
 Bend, OR 97701
 Tel: (503) 325-8811
 Fax: (503) 325-8811

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

Jeff Wellman
 Project Superintendent
 Kirby Nagelroth Construction Co.
 3800 SW 10th Ave
 Bend, OR 97701
 Tel: (503) 325-8811
 Fax: (503) 325-8811

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867

RFI #1

STEELE ASSOCIATES ARCHITECTS
 180 NW York Dr., Suite 200
 Bend, Oregon 97701
 Tel: (503) 382-9867
 Fax: (503) 382-9867


INCOMING ELECTRICAL SERVICE DIVISION OF RESPONSIBILITY					
	ELEC. CONTR.	UTILITY CO.	ELEC. CONTR.	UTILITY CO.	
PRIMARY CONDUIT	<input checked="" type="checkbox"/>	<input type="checkbox"/>	SECONDARY CONDUIT	<input checked="" type="checkbox"/>	<input type="checkbox"/>
PRIMARY CONDUCTORS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SECONDARY CONDUCTORS	<input checked="" type="checkbox"/>	<input type="checkbox"/>
TRANSFORMER	<input type="checkbox"/>	<input checked="" type="checkbox"/>	C/T ENCLOSURE	<input checked="" type="checkbox"/>	<input type="checkbox"/>
XMR PAD/VAULT	<input checked="" type="checkbox"/>	<input type="checkbox"/>	C/T's	<input type="checkbox"/>	<input checked="" type="checkbox"/>
BOLLARDS	<input checked="" type="checkbox"/>	<input type="checkbox"/>	METER BASE	<input checked="" type="checkbox"/>	<input type="checkbox"/>
TRANSFORMER CONNECTIONS	<input type="checkbox"/>	<input checked="" type="checkbox"/>	METER	<input type="checkbox"/>	<input checked="" type="checkbox"/>

NOTES:
 1. THE ELECTRICAL CONTRACTOR SHALL CONTACT AND COORDINATE ALL REQUIREMENTS AND RESPONSIBILITIES WITH UTILITY CO. PRIOR TO SUBMITTING BID.


POWER UTILITY CONTACT:
 CENTRAL ELECTRIC COOPERATIVE
 LANCE WOODERSON
 2025 N HWY 97, PO BOX 846
 REDMOND, OR 97756
 PHONE: (541) 517-7738
 FAX: (541) 546-0369
 wooderson@cec.coop

PHONE UTILITY CONTACT:
 QWEST
 TRAVIS VAUGHN
 100 NW KEARNEY AVE
 BEND, OR 97701
 PHONE: (541) 385-0298
 FAX: (541) 385-0228
 travis.vaughn@qwest.com

- SHEET KEYNOTES**
- SEE ONE-LINE FOR FEEDER SIZING.
 - PROVIDE TWO 1" CONDUITS TO THE FIRE SPRINKLER VAULT. PROVIDE ONE CONDUIT FOR POWER CONNECTION TO SUMP PUMP. PROVIDE ONE EMPTY CONDUIT WITH PULL CORD FOR FUTURE CONNECTION TO TAMPER SWITCHES. INTERCONNECT TAMPER SWITCHES AND PIV WITH 1" CONDUIT. COORDINATE LOCATION OF PIV PRIOR TO ROUGH-IN.
 - ROUTE CONDUITS IN JOINT TRENCH WITH THE ELECTRICAL UTILITY CONDUITS. MAINTAIN CONDUIT SPACING PER UTILITY REQUIREMENTS.
 - PROVIDE TWO THERMAL RAYCHEM ELECTROMELT SURFACE SNOW MELTING SYSTEM WITH AMBIENT AIR THERMOSTAT AND MOISTURE SENSOR FOR CONTROL. COORDINATE AND INSTALL EQUIPMENT PER MANUFACTURER REQUIREMENTS.
 - ROUTE CONDUIT TO SNOW MELT SYSTEM CONTROL PANEL. SEE THE ONE-LINE FOR FEEDER SIZING.
 - PROVIDE A 30"x43" PULL BOX. UTILITY VAULT 1750-18 BOX AND COVER OR APPROVED.
 - PROVIDE A POWER CONNECTION TO THE FLAG POLE POST TOP LUMINAIRE. COORDINATE THE EXACT LOCATION PRIOR TO ROUGH-IN.
 - PROVIDE A UTILITY VAULT. MODEL U.V. #687-2-CEC WITH A CS LID, U.V. MODEL # 687 W/2-332P C-OFFSET; 135B BO & INSERTS.
 - PROVIDE A UTILITY VAULT. MODEL U.V. #687-2-CEC WITH A C11 LID, U.V. MODEL # 6'-8"X9'-1"X8" SLAB W/2436P, 1254 & 1360 BLOCKOUTS.
 - PROVIDE A UTILITY VAULT FOR THE TELEPHONE SERVICE COMMUNICATION CABLES. PROVIDE U.V. 264-TA WITH A No. 264P ADJUSTABLE FRAME COVER AND GALVANIZED DIAMOND PLATE DOORS.
 - PROVIDE CITY TRAIL LIGHT POLE WITH INTERCONNECTING 2" CONDUIT. PROVIDE PULL CORD IN ALL CONDUIT RUNS. CONDUCTORS PROVIDED BY OTHERS. PROVIDE ONE 1" CONDUIT FROM J-BOX TO NEW TRAIL LIGHTING POLE. LOCATE POLE BASE A MINIMUM OF 2' BACK FROM FACE OF CURB.



1 SITE PLAN - ELECTRICAL
 SCALE: 1"=20'-0"



STEELE ASSOCIATES ARCHITECTS LLC
 760 NW YORK DRIVE, SUITE 200
 BEND, OR 97701
 541.382.9867
 info@steele-arch.com

REGISTERED PROFESSIONAL ENGINEER
 KENNETH W. STEELE
 EXPIRES: 06/30/12

COCC MADRAS CAMPUS EDUCATION CENTER
 ASHWOOD ROAD
 MADRAS, OREGON

SITE PLAN - ELECTRICAL

PROJECT 2010-0323
CONTACT Michael Slevcove

DATE 10/20/10
DESIGNED BY MJS
CHECKED BY AG, MJS

DATE 10/20/10

PROJECT 2010-0323
CONTACT Michael Slevcove

INTERFACE ENGINEERING
 708 SW Third Avenue
 Suite 400
 Portland, OR 97204
 TEL: 503.382.2286
 FAX: 503.382.2262
 www.interfaceengineering.com

E102

CONSTRUCTION SET - 02/11/11

ZONE LIGHTING CONTROL SCHEDULE

ZONE NUMBER	DESCRIPTION	INPUTS	KEYPAD TYPE	BUTTON	TEXT	FUNCTION
1	Hallways/Corridors	Low Voltage Switches Time Clock	One button	1	ON	All area lighting ON during building's occupied hours per timeclock schedule; lights blink 5 minutes prior to being swept off. Provide a 2hr override delay if button is pressed after lights blink prior to being swept off. After 5 minutes and no override input, turn all lights off once outside building occupied hours per Owner's schedule. See the drawings for the quantity and locations of the override low voltage switches.
2	Exterior	Low Voltage Switch Open Loop Photoceill Time Clock	Two button	1 2	ON OFF	Override Switch: All normal exterior lighting ON. Override switch: All normal exterior lighting OFF. ON per exterior photo sensor OFF per Owner defined schedule.
3	Lobby	Time Clock ZONE 1 Button				All area lighting ON during building's occupied hours per timeclock schedule; lights blink 5 minutes prior to being swept off. Provide a 2hr override delay if button is pressed after lights blink prior to being swept off. After 5 minutes and no override input, turn all lights off once outside building occupied hours per Owner's schedule. See the drawings for the quantity and locations of the override low voltage switches.

MECHANICAL EQUIPMENT CONNECTION SCHEDULE

ITEM	DESCRIPTION	LOCATION	VOLTS / PHASE	LOAD	MCA	MOCPP	WIRE / CONDUIT	CIRCUIT	NOTES
F-1	GAS FURNACE	MECH/ELEC. RM	120/1		18.4	30	302	2M-1.	1.
F-2	GAS FURNACE	MECH/ELEC. RM	120/1		13.4	20	202	2M-3.	1.
F-3	GAS FURNACE	MECH/ELEC. RM	120/1		18.4	30	302	2M-5.	1.
F-4	GAS FURNACE	MECH/ELEC. RM	120/1		13.4	20	202	2M-7.	1.
F-5	GAS FURNACE	MECH/ELEC. RM	120/1		18.4	30	302	2M-9.	1.
F-6	GAS FURNACE	MECH/ELEC. RM	120/1		10.0	20	202	2M-11.	1.
F-7	GAS FURNACE	MECH/ELEC. RM	120/1		12.8	20	202	2M-13.	1.
F-8	GAS FURNACE	MECH/ELEC. RM	120/1		12.8	20	202	2M-15.	1.
F-9	GAS FURNACE	MECH/ELEC. RM	120/1		18.4	30	302	2M-17.	1.
CU-1	CONDENSING UNIT	ROOF	208/1		34.3	50	502	2M-19,21.	
CU-2	CONDENSING UNIT	ROOF	208/1		23.7	40	402	2M-23,25.	
CU-3	CONDENSING UNIT	ROOF	208/1		34.3	50	502	2M-27,29.	
CU-4	CONDENSING UNIT	ROOF	208/1		23.7	40	402	2M-31,33.	
CU-5	CONDENSING UNIT	ROOF	208/1		28.5	45	502	2M-35,37.	
CU-6	CONDENSING UNIT	ROOF	208/1		17.5	25	302	2M-39,41.	
CU-7	CONDENSING UNIT	ROOF	208/1		21.9	35	402	2M-2,4.	
CU-8	CONDENSING UNIT	ROOF	208/1		21.9	35	402	2M-6,8.	
CU-9	CONDENSING UNIT	ROOF	208/1		34.3	50	502	2M-10,12.	
EW-1	ELECTRIC WALL HEATER	FIRE RISER ROOM	120/1	1.0 KW			202	2M-16.	
ACU-1	AIR CONDITIONING UNIT	ROOF	208/1		13	20	202	2M-18,20.	
AF-1	AIR CONDITIONING UNIT	IT ROOM	208/1				202	---	2.
EF-1	EXHAUST FAN	ROOF	120/1	0.2 HP			202	2M-14.	
EF-2	EXHAUST FAN	MECH/ELEC. RM	120/1	0.5 HP			202	2M-36.	
EF-3	EXHAUST FAN	MECH/ELEC. RM	120/1	0.5 HP			202	2M-38.	
EF-4	EXHAUST FAN	JAN. 124 (ALT. PLAN)	120/1	200 W			202	2M-40.	
SP-1A	SUMP PUMP	MECH/ELEC. RM	120/1	0.3 HP			202	2M-22.	
SP-1B	SUMP PUMP	MECH/ELEC. RM	120/1	0.3 HP			202	2M-24.	
WH-1	WATER HEATER	JAN. 124	208/1	4.5 KW			402	2M-26,28.	
WH-2	WATER HEATER	ADMIN. KITCHEN	120/1	1.5 KW	12.5	20	202	2M-30.	
WH-3	WATER HEATER	CLASSROOM 2	120/1	1.5 KW	12.5	20	202	2M-32.	

GENERAL MECHANICAL EQUIPMENT CONNECTION SCHEDULE NOTES

A. THE ABOVE INFORMATION IS FOR A SPECIFIC MANUFACTURER. ACTUAL MANUFACTURER FOR EQUIPMENT MAY BE DIFFERENT. COORDINATE WITH MECHANICAL EQUIPMENT SUBMITTALS FOR LOADS AND OVER CURRENT PROTECTION REQUIREMENTS PRIOR TO INSTALLATION OF WIRING.

B. MOCPP = MAXIMUM OVER CURRENT PROTECTION
MCA = MINIMUM CIRCUIT AMPACITY

MECHANICAL EQUIPMENT CONNECTION SCHEDULE NOTES

1. PROVIDE A NEMA 5-15P CORD CAP FOR EACH FURNACE CONDENSATE PUMPS.
2. PROVIDE POWER CONNECTION FROM OUTDOOR UNIT.

COPPER FEEDER SCHEDULE

202 2 #12 CU, 1 #12 CU GND., IN 3/4" C.
302 2 #10 CU, 1 #10 CU GND., IN 3/4" C.
402 2 #8 CU, 1 #10 CU GND., IN 3/4" C.
502 2 #6 CU, 1 #10 CU GND., IN 3/4" C.

LIGHTING CONTROL CABINET RELAY PANEL 1,0PF

RELAY	CIRCUIT	DESCRIPTION	CONTROL	ZONE	NOTES
1	2A-4,6	PARKING LOT POLE TOP LTG.	TC,PC,CLV	2	1.
2	2A-4	FLD POLE TOP LTG.	TC,PC,CLV	2	
3	2A-8	EXC. BUILDING MOUNTED LTG.	TC,PC,CLV	2	
4	2A-12	ROOF TOP HOLIDAY LTG. RECEIPTABLES	TC,PC,CLV	2	
5	2A-14	ROOF TOP HOLIDAY LTG. RECEIPTABLES	TC,PC,CLV	2	
6	2A-16	ROOF TOP HOLIDAY LTG. RECEIPTABLES	TC,PC,CLV	2	
7	2A-18	HALLWAY	TCLV	1	
8	2A-20	LOBBY	TCLV	3	
9	2A-22	LOBBY-ROPE LIGHT	TCLV	3	
10	2A-24	LOBBY-ROPE LIGHT	TCLV	3	
11					
12					
13					
14					
15					
16					
17					

ENCLOSURE:
FLUSH SURFACE _____
NEMA RATING _____

NOTES:
1) PROVIDE A 2-POLE RELAY.

CONTROLS:
TC TIMECLOCK
PC PHOTOCELL
LV LOW VOLTAGE SWITCH

KIRBY NAGELBOIT CONSTRUCTION COMPANY
1000 NE 11th St
Portland, OR 97232
Tel: 503.251.1111 Fax: 503.251.1112

STEELE ASSOCIATES ARCHITECTS
760 NW York Dr., Suite 200
Bend, Oregon 97701
Tel: 541.382.9867 Fax: 541.382.9868

RFI # 57
Date: 9/22/11
Job: 2010-0323 Madras Campus
Phase: 1E2

Subject: Panel 2A SPD
Drawing: 0402-1000
Contract: 100

Request: Submittal Review for panel 2A under 2010-0323 Low Voltage Electrical Distribution System Panel 2A. Provide with stamped approval. Panel 2A has no other panel connected to it so the only load is the building. Provide SPD. Provide cost of approximately \$1000. Please confirm if SPD is required on Panel 2A.

Requested by: Chris Peck
KIRBY NAGELBOIT

Response: Owner as selected to not install a SPD on panel 2A.
Steve Olson
9/17/11

KIRBY NAGELBOIT CONSTRUCTION COMPANY
1000 NE 11th St
Portland, OR 97232
Tel: 503.251.1111 Fax: 503.251.1112

STEELE ASSOCIATES ARCHITECTS
760 NW York Dr., Suite 200
Bend, Oregon 97701
Tel: 541.382.9867 Fax: 541.382.9868

RFI # 44
Date: 9/22/11
Job: 2010-0323 Madras Campus
Phase: 1E2

Subject: LCP OR Size Control
Drawing: LCP OR Size Control
Contract: 100

Request: The schedule 2010-0323 L.A. 2 and LCP to be implemented through after the 10-02-2011 and through the month of October. Submittal review for panel 2A. Please provide light time and with reason for the size control. This LCP modification is to be implemented and a model shown that is not currently installed to be coordinated with the schedule. To verify the panel is on the COCC network need to be approximately 8000 additional costs. Please advise.

Requested by: Chris Peck
KIRBY NAGELBOIT

Response: SEE PR-21.
JAMES TAYLOR
9/22/11

Panel '2A'

120/208V, 3 Ph., 4 W.; 200A Bus with Main Lug Only 2010-0323 COCC
Surface Mounted, Lighting & Appliance Branch Panelboard Available Fault: 14695A RMS

Ckt. No.	Description / Location	Load (VA) Type	C.B. A/Pole	Note	Ph.	Note	C.B. A/Pole	Load (VA) Type	Description / Location	Ckt. No.
1	FIRE SPRINKLER VLT SUMP PUMP	500 R	20/1		A		20/1	1,000 L	LG. CONT. PNL. LCP1	2
3	FACP	1,000 R	20/1		B		20/2	450 L	EXTERIOR PARKING LOT LTG.	4
5	IRRIGATION CONTROLLER	500 R	20/1		C			320 L		6
7	R-TELECOM DEMARK	400 R	20/1		A		20/1	800 L	BUILDING MOUNTED LTG.	8
9	R-TELECOM DEMARK	400 R	20/1		B		20/1	400 L	L-BASMENT	10
11	R-MECH/ELEC. RM	600 R	20/1		C		20/1	400 R	R-ROOF TOP HOLIDAY LTG.	12
13	R-MECH/ELEC. RM	600 R	20/1		A		20/1	400 R	R-ROOF TOP HOLIDAY LTG.	14
15	R-OFFICE 110	1,000 R	20/1		B		20/1	400 R	R-ROOF TOP HOLIDAY LTG.	16
17	R-ADMIN. 106	1,000 R	20/1		C		20/1	700 L	L-HALL WAY	18
19	R-ADMIN. 106	800 R	20/1		A		20/1	1,200 L	L-LOBBY	20
21	R-CLASSROOM 114	1,200 R	20/1		B		20/1	1,000 L	L-ROPE LIGHT	22
23	R-CLASSROOM 114	1,200 R	20/1		C		20/1	1,000 L	L-ROPE LIGHT	24
25	R-CLASSROOM 114	1,100 R	20/1		A		20/1	1,460 L	L-ADMIN AREA / OFFICES	26
27	R-CLASSROOM 115	1,200 R	20/1		B		20/1	1,150 L	L-RECEPTION / RESTROOMS	28
29	R-CLASSROOM 115	1,200 R	20/1		C		20/1	1,440 L	L-CLASSROOMS	30
31	R-CLASSROOM 115	1,100 R	20/1		A		20/1	1,510 L	L-COMMUNITY ROOM	32
33	R-CLASSROOM 116	1,200 R	20/1		B		20/1	1,000 L	L-COMPUTER LAB	34
35	R-CLASSROOM 116	1,000 R	20/1		C		20/1		SPARE	36
37	R-CLASSROOM 116	1,000 R	20/1		A		20/1		SPARE	38
39	R-COMMUNITY ROOM 117	1,000 R	20/1		B		20/1	600 R	R-ADMIN. KITCHEN	40
41	R-COMMUNITY ROOM 117	800 R	20/1		C		20/1	1,000 R	R-ADMIN. KITCHEN	42
43	R-COMMUNITY ROOM 117	1,000 R	20/1		A		20/1	200 R	R-ADMIN. KITCHEN	44
45	R-STUDENT STUDY	1,000 R	20/1		B		20/1	1,000 R	R-TESTING 104	46
47	R-COMPUTER LAB	1,000 R	20/1		C		20/1	1,000 R	R-TESTING 104	48
49	R-COMPUTER LAB	1,000 R	20/1		A		20/1	1,000 R	R-VENDING MACHINE	50
51	R-COMPUTER LAB	1,000 R	20/1		B		20/1	1,000 R	R-VENDING MACHINE	52
53	R-COMPUTER LAB	800 R	20/1		C		20/1	800 R	R-OFFICE 109	54
55	R-COMPUTER LAB	800 R	20/1		A		20/1	800 R	R-OFFICE 108	56
57	R-COMPUTER LAB	800 R	20/1		B		20/1	600 R	R-OFFICE 107	58
59	R-COMPUTER LAB	800 R	20/1		C		20/1	600 R	R-OFFICE 107	60
61	R-HALL	1,000 R	20/1		A		20/1		SPARE	62
63	R-HALL	600 R	20/1		B		20/1		SPARE	64
65	SPARE		20/1		C		20/1		SPARE	66

Total Connected Load: Ph. A 17,670 VA 147 Amps Panel Connected Load: 51.8 KVA 144.0 Amps
Total Connected Load: Ph. B 18,000 VA 150 Amps Sub-Fed Connected Load: 0.0 KVA 0.0 Amps
Total Connected Load: Ph. C 16,180 VA 135 Amps Total Demand Load: 41.0 KVA 113.9 Amps

Notes:
1.
2.
3.
4.
5.

Panel '2B'

120/208V, 3 Ph., 4 W.; 200A Bus with Main Lug Only 2010-0323 COCC
Surface Mounted, Lighting & Appliance Branch Panelboard Available Fault: 14271A RMS

Ckt. No.	Description / Location	Load (VA) Type	C.B. A/Pole	Note	Ph.	Note	C.B. A/Pole	Load (VA) Type	Description / Location	Ckt. No.
1	R-STUDENT ADVISOR 111	800 R	20/1		A		20/1			2
3	R-TUTOR 105 / DIRECTOR 103	1,000 R	20/1		B		20/1			4
5	R-RECEPTION 102	1,000 R	20/1		C		20/1			6
7	R-I.T. 125	400 R	20/1		A		20/1			8
9	R-I.T. 125	800 R	20/1		B		20/1			10
11	R-I.T. 125	800 R	20/1		C		20/1			12
13	R-LOBBY 101 / HALL	1,000 R	20/1		A		20/1			14
15	R-MENS / WOMENS RESTROOM	1,200 R	20/1		B		20/1			16
17	R-MENS RESTROOM FLUSH VLV	500 R	20/1		C		20/1			18
19	R-WOMENS REST. FLUSH VLV	500 R	20/1		A		20/1			20
21					B		20/1			22
23					C		20/1			24
25					A					26
27					B					28
29					C					30
31					A					32
33					B					34
35					C					36
37					A					38
39					B					40
41					C					42

Total Connected Load: Ph. A 2,700 VA 23 Amps Panel Connected Load: 8.0 KVA 22.2 Amps
Total Connected Load: Ph. B 3,000 VA 25 Amps Sub-Fed Connected Load: 0.0 KVA 0.0 Amps
Total Connected Load: Ph. C 2,300 VA 19 Amps Total Demand Load: 8.0 KVA 22.2 Amps

Notes:
1.
2.
3.
4.
5.

Panel '2M'

120/208V, 3 Ph., 4 W.; 225A Bus with Main Lug Only 2010-0323 COCC
Surface Mounted, Lighting & Appliance Branch Panelboard Available Fault: 13868A RMS

Ckt. No.	Description / Location	Load (VA) Type	C.B. A/Pole	Note	Ph.	Note	C.B. A/Pole	Load (VA) Type	Description / Location	Ckt. No.
1	F-1	1,800 M	30/1		A		35/2	1,850 M	CU-7	2
3	F-2	1,300 M	20/1		B			1,850 M		4
5	F-3	1,800 M	30/1		C		35/2	1,850 M	CU-8	6
7	F-4	1,300 M	20/1		A			1,850 M		8
9	F-5	1,800 M	30/1		B		50/2	2,900 M	CU-9	10
11	F-6	960 M	20/1		C			2,900 M		12
13	F-7	1,250 M	20/1		A		20/1	700 M	EF-1	14
15	F-8	1,250 M	20/1		B		20/1	1,000 H	EW-1	16
17	F-9	1,800 M	30/1		C		20/2	1,200 M	ACU-1	18
19	CU-1	2,900 M	50/2		A			1,200 M		20
21		2,900 M			B		20/1	900 M	SP-1A	22
23	CU-2	2,000 M	40/2		C		20/1	900 M	SP-1B	24
25		2,000 M			A		40/2	2,250 WH	WH-1	26
27	CU-3	2,900 M	50/2		B			2,250 WH		28
29		2,900 M			C		20/1	1,500 WH	WH-2	30
31	CU-4	2,000 M	40/2		A		20/1	1,500 WH	WH-3	32
33		2,000 M			B		20/1	600 R	ROOF TOP MAINTENANCE RECEPT.	34
35	CU-5	2,400 M	45/2		C		20/1	1,175 M	EF-2	36
37		2,400 M</								